# Appendix-I

## **Timeline for completion of Projects**

(Refer to Regulation 24)

- 1. The completion time schedule shall be reckoned from the date of investment approval by the Board (of the generating company or the transmission licensee), or the CCEA clearance as the case may be, up to the date of commercial operation of the units or block or element of transmission project as applicable.
- 2. The time schedule has been indicated in months in the following paragraphs and tables:

### A. Thermal Power Projects

## **Coal/Lignite Power Plant**

Unit size 200/210/250/300/330 MW and 125 MW CFBC technology

- (a) 33 months for green field projects. Subsequent units at an interval of 4 months each.
- (b) 31 months for extension projects. Subsequent units at an interval of 4 months each.

Unit size 250 MW CFBC technology

- (a) 36 months for green field projects. Subsequent units at an interval of 4 months each.
- (b) 34 months for extension projects. Subsequent units at an interval of 4 months each.

Unit size 500/600 MW

- (a) 44 months for green field projects. Subsequent units at an interval of 6 months each.
- (b) 42 months for extension projects. Subsequent units at an interval of 6 months each.

Unit size 660/800 MW

- (a) 52 months for green field projects. Subsequent units at an interval of 6 months each.
- (b) 50 months for extension projects. Subsequent units at an interval of 6 months each.

#### **Combined Cycle Power Plant**

Gas Turbine size upto 100 MW (ISO rating)

- (a) 26 months for first block of green field projects. Subsequent blocks at an interval of 2 months each.
- (b) 24 months for first block of extension projects. Subsequent units at an interval of 2 months each.

Gas Turbine size above 100 MW (ISO rating)

- (a) 30 months for first block of green field projects. Subsequent blocks at an interval of 4 months each.
- (b) 28 months for first block of extension projects. Subsequent units at an interval of 4 months each.

## **B.** Hydro Electric Projects

The qualifying time schedule for hydro electric projects shall be as stated in the original concurrence issued by the Central Electricity Authority under section 8 of the Act.

# C. Transmission Schemes

Qualifying time schedules in months

Sr.	Transmission Work	Plain	Hilly	Snowbound
No.		Area	Terrain	area/@very
		(months)	(months)	difficult
				Terrain
				(months)
a	765 kV S/C Transmission line	30	36	40
b	765 kV D/C Transmission line	34	40	44
С	+/-500 KV HVDC	24	30	34
	Transmission line			
d	400 KV M/C Quad or more	34	40	44
	sub-conductor Transmission			
	line			
e	400 KV M/C Twin/Triple	32	38	42
	Transmission line			
f	400 KV D/C Quad	32	38	42
	Transmission line			
g	400 KV D/C Triple	30	36	40
	Transmission line			
h	400 KV D/C Twin	28	34	38
	Transmission line			
i	400 KV S/C Six or more sub-	30	36	40
	conductor Transmission line			
j	400 KV S/C Twin	24	30	34
	Transmission line			
k	220 KV D/C Twin	28	34	38
	Transmission line			
1	220 KV D/C Transmission line	24	30	34

Sr.	Transmission Work	Plain	Hilly	Snowbound		
No.		Area	Terrain	area/@very		
		(months)	(months)	difficult		
				Terrain		
				(months)		
m	220 KV S/C Transmission line	20	26	30		
n	New 220 KV AC Sub-Station	18	21	24		
О	New 400 KV AC Sub-Station	24	27	30		
р	New 765 kV AC Sub-Station	30	34	\$		
q	*HVDC bi-pole terminal	36	38	-		
r	HVDC back-to-back	26	28	-		
<sup>®</sup> e.g. Leh, Laddakh						
\$ No 765 kV sub-station has been planned in difficult terrain						
*Includes <u>+</u> 800 kV HVDC bi-pole terminal						

#### Notes:

- (i) In case a scheme having combination of the above mentioned types of projects, the qualifying time schedule of the activity having maximum time period shall be considered for the scheme as a whole.
- (ii) In case a transmission line falls in plain as well as in hilly terrain/snow bound area/very difficult terrain, the composite qualifying time schedule shall be calculated giving proportional weightage to the line length falling in each area.