



केन्द्रीय विद्युत विनियामक आयोग
CENTRAL ELECTRICITY REGULATORY COMMISSION
**Ground Floor, Chanderlok Building,
36, Janpath, New Delhi -110 001**



ADMN-11017/9/2021-CERC

Dated, the 22nd March, 2023

To,

- (1) M/s MAK Enterprises
WZ-33A, Ground Floor,
Meenakshi Garden, New Delhi-110018
- (2) M/s Satyam Furniture House
Shop No. 9 to 11, Plot No. 7,
Sewak Park Extn. Near Metro Pillar No. 760,
New Delhi-110059
- (3) M/s U-Like Furnishing
Shop No. 9, Khasra No. 897 to 903/105,
Village Nawada Mazra Hastal, Gulab Bagh,
Uttam Nagar, New Delhi-110059
- (4) M/s Vikas Enterprises
A-112, Mansa Ram Park,
Uttam Nagar, New Delhi-110059

Sub: Quotation required for repair of Ladies & Gents Toilet on 3rd Floor (Engg. Side), at CERC office, Chanderlok Building, Janpath, New Delhi-110001

Central Electricity Regulatory Commission, a statutory body set up under an Act of Parliament, invites sealed quotations from NDMC/CPWD/PWD registered vendors for repair of Ladies & Gents Toilet at 3rd Floor (Engg. Side), at CERC office, Chanderlok Building, Janpath, New Delhi-110001.

2. The detailed scope of work and quantity of materials required are given below:-

2.1 **Scope of Work.** The whole work is to be considered as a Turnkey project. The firm which will be awarded the contract, shall complete the whole work, the details is as under: -

(i) The Ladies & Gents Toilets at 3rd Floor (Engg. Side) shall be repair i.e. New tilling work in floor area of toilet after repair of leakages and seepages, excluding sanitary fixtures i.e. wash basin, toilet sheet & urinal basin etc., including supply of required materials.

(ii) Repair of shaft also considered at 3rd floors Ladies & Gents Toilets (Engg. Side) area and hand it over to CERC in a fully functional state.

2.2 List of items and other details is as under:-

Items required for 3 rd Floor Ladies Washroom		
Sl. No.	Particulars	Quantity
1	PVC 1" Pipe (each length for 10')	10.00
2	1"x3/4 T Plain	10.00
3	1" Socket	10.00
4	1" Elbow .	8.00
5	1"x 3/4" F. Elbow	8.00
6	1/2"x3/4" Plane F. Elbow	15.00
7	3/4" Pipe	6.00
8	3/4" Cross Over Band	4.00
9	1/2" x3/4" F. Socket	6.00
10	1/2"x3/4" F T	6.00
11	1/2" Plug	10.00
12	3/4" 25mm Sedal	1.00
13	CPVC Solvent (237 gm)	1.00
14	4" Pipe	15 Ft
15	4" Elbow	7.00
16	4" Trap	2.00
17	4" Tee	3.00
18	Solvent	1.00
19	M Seal (Big 200gm)	2.00
20	Tiles (for Thickness of tiles 10mm to 25mm)	40 Sq. ft
21	Tiles Grouter	2.00
22	Dust	70 ft
23	Concrete	50 ft
23	Cement ISI Mark (50kg each bag)	10 bag
24	Dismantling of tile work in floors in cement mortar including stacking material.	Complete floor Work of 3 rd Floor ladies Toilet (Engg. Side) Area
25	Repairing of all damage/seepage area, waterproof work of complete 3 rd floor Ladies Toilet (Engg. Side)	3 rd Floor ladies Toilet (Engg. Side) Area
26	Refilling of Filling material in sunken portion from Ground floor to 3 rd floor using stairs	3 rd Floor ladies Toilet (Engg. Side) Area
27	Disposal of Malba from site (i.e Chanderlok Building, 36, Janpath, New Delhi)	3 rd Floor ladies Toilet (Engg. Side) Area
28	Misc Expenses (if any) (i.e. Misc Items, Labour charges and any other items required for repairing work, etc.)	3 rd Floor ladies Toilet (Engg. Side) Area

Items Required for 3 rd Floor Ladies & Gents Washroom (if both washrooms are required to be repair)		
Sl. No.	Particulars	Quantity
1	PVC 1" Pipe (each length for 10')	25.00
2	1"x3/4 T Plain	15.00
3	1" Socket	15.00
4	1" Elbow .	12.00
5	1"x 3/4" F. Elbow	20.00
6	1/2"x3/4" Plane F. Elbow	30.00
7	3/4" Pipe	12.00
8	3/4" Cross Over Band	8.00
9	1/2" x3/4" F. Socket	12.00
10	1/2"x3/4" F T	12.00
11	1/2" Plug	24.00
12	3/4" 25mm Sedal	2.00
13	CPVC Solvent (500 gm)	2.00
14	4" Pipe	60 Ft
15	4" Elbow	12.00
16	4" Half Set	4.00
17	4" Tee	8.00
18	4" Socket	8.00
19	4" Trap	4.00
20	4 1/4 " Pipe	25 Ft
21	4 1/4 " Elbow	15.00
22	Solvent	2Ltr
23	M Seal (Big 200gm)	3.00
24	Tiles (for Thickness of tiles 10mm to 25mm)	110 Sq. ft
25	Tiles Grouter	4.00
26	Dust	150 ft
27	Concreate	80 ft
28	Cement ISI Mark (50kg each bag)	25 bag
29	Dismantling tile work in floors in cement mortar including stacking material within 50 metres lead.	Complete floor Work of 3 rd Floor ladies & Gents Toilet Area
30	Repairing of all damage/seepage area, waterproof work of complete 3 rd floor Ladies & Gents Toilet (Engg. Side)	3 rd Floor ladies & Gents Toilet Area

31	Refilling of Filling material in sunken portion from Ground floor to 3rd floor using stairs	3 rd Floor ladies & Gents Toilet Area
32	Disposal of Malba from site (i.e Chanderlok Building, 36, Janpath, New Delhi)	3 rd Floor ladies & Gents Toilet Area
33	Misc Expenses (if any) (like; Misc Items/Materials, Labour charges and any other items required for repairing work etc.)	3 rd Floor ladies & Gents Toilet Area

3. Terms & Conditions

3.1 NDMC/CPWD/PWD registered Contractors in Composite Categories shall be eligible to participate in Quotation Process.

3.2 The work shall be carried out as per **relevant** NDMC/CPWD/PWD General Specifications for Civil works etc.

3.3 No T & P shall be issued by the department.

3.4 Free water and power supply shall be supplied to the contractor by the department during the above repair work, installation, testing and commissioning period.

3.5 The rates quoted shall be inclusive of all Taxes and duties, nothing extra shall be paid on this Account.

3.6 The contractor shall be responsible for the engagement of labour keeping in view the work, site and time period for completion of work assigned.

3.7 Any damage to the existing fittings shall be replaced by the contractor at his own cost and risk, to the entire satisfaction of the Assistant Secretary (P&A), CERC.

3.8 Increase/decrease in the quantity of material, if any, be paid/adjusted as per unit rates mentioned at para 2.2 above at the time of releasing the payment.

3.9 The makes of material will be as per undermentioned list of approved makes against each item of work.

3.10 Contractor shall be responsible for conduct of staff/workers deployed at site of work.

3.11 If any item is to be different than whatever mentioned in the schedule of work it should specifically be brought out to the notice of department while quoting for the tender.

3.12 The work is to be carried out in a building having very strict regulations. The persons engaged in work must have good character antecedents. The contractor should familiarize himself with the process of obtaining entry passes/entry tokens etc.

- 3.13 No claim for wastage of labour due to non-issuance of entry token/entry passes shall be considered by the Department.
- 3.14 The agency is required to complete work within 30 days {on working days 06:30 PM onward & full day on Saturday, Sunday & closed holidays) from the date of award of contract.
- 3.15 The firm must have a valid PAN Number (self-attested copy to be attached).
- 3.16 The firm must have a valid GST Number (self-attested copy to be attached).
4. The bidder shall submit an undertaking in support of the claim that he/she has not been blacklisted during the last three years by any organizations/ Government Departments.
5. Evaluation of bid would be on the basis of lowest rate quoted.
6. The prices should be inclusive of cartage and transportation of goods etc. CERC will not pay any extra charges for cartage and transportation of goods. GST, if any, shall be payable extra.
7. The agency is required to complete work within 30 days from the date of award of contract.
8. Before quoting the rates, the bidders may inspect the site on any working day from **24th March, 2023 to 28th March, 2023** between **10.00 AM to 13.00 Noon** only (Except Sunday).
9. **TOOLS and EQUIPMENTS** - The agency shall arrange at its own expenses all necessary tools, equipment's and required parts for proper execution of the work.
10. **SATISFACTORY SERVICES** - The decisions of Assistant Secretary (P&A), CERC or any other officer authorized by the Secretary, CERC, shall be final and binding on the firm / agency for the purpose of determining satisfactory services.
11. **PROHIBITION OF SUB CONTRACT** - The firm / agency shall not appoint any sub-contract for this work under any circumstances.
12. The payment shall be released through RTGS/NEFT after satisfactory completion of entire work. No advance payment will be made in any case.
13. **DEDUCTION OF INCOME TAX AT SOURCE** - Since it is a "Works Job Order", Income Tax shall be deducted at source from all the accepted payment to be made, in accordance with the provision of Income Tax Act, 1961 as amended from time to time.
14. **RESOLUTION OF DISPUTE** - In case of dispute the decisions of Secretary, CERC shall be final.
15. In case of any accident/misshaping/misfirer with any labour on project site, all the responsibility shall be borne by the contractor nothing shall be on the part of CERC in this regard.

16. **Penalty Clause's:** - In case of failure on the part of agency or delay in completion of work, the CERC shall have the discretion to get it rectified/ completed from other sources at contractor's risk and cost.

17. Quotations strictly as per the above specification may kindly be sent to the undersigned in sealed cover on or before the **31st March, 2023, up to 15.00 hrs.**

18. The Secretary, CERC reserves the right to accept or reject any or all the quotations without assigning any reason whatsoever.



(Sachin Kumar)

Assistant Secretary (P&A)

Tel: 23793921

DECLARATION

To,

The Assistant Secretary (P&A),
Central Electricity Regulatory Commission,
3rd Floor, Chanderlok Building,
36, Janpath, New Delhi-110001.

Sir,

I have actually inspected the site on _____ and have carefully gone through the Terms & Conditions contained in the Tender Document No. **ADMN-11017/9/2021-CERC** dated 22nd March, 2023. I hereby declare that my firm has not been debarred/black listed by any reputed Government / Semi Government organizations for quality/ service products within the last three years nor is there any pending dispute regarding short shipment/ installation/service. I further certify that I am an authorized signatory of my company/firm and am, therefore, competent to make this declaration.

Yours sincerely,

Name: _____

Designation : _____

Company/firm: _____

Address: _____

CENTRAL ELECTRICITY REGULATORY COMMISSION

**Quotation for repair/renovation of Ladies & Gents Toilet at 3rd Floor
(Engg. Side), at CERC office, Chanderlok Building, Janpath,
New Delhi-110001**

1. Name of the Firm _____
2. Address _____
3. Telephone No: _____ Fax No. _____

Sl. No.	Description	Rate quoted	Remarks (if any)
(A) For Repairing of Ladies Toilet of 3rd Floor (Engg.Side) only			
(a)	Cost of consumable and miscellanies items for repair/renovation of Ladies Toilet at 3 rd Floor (Engg. Side) and installation/fitting charges as per Annexure -II. (if Repair only Ladies Toilet)		
(b)	MISC Charges if any (i.e. Misc. Items, Labour charges and other items required for repairing work etc.)		
	Sub Total		
	Total GST Charge for above items and works		
	Grand Total		
(B) For Repairing of Ladies & Gents Toilets of 3rd Floor (Engg. Side)			
(a)	Cost of consumable and miscellanies items for repair/renovation of Ladies & Gents Toilet at 3 rd Floor (Engg. Side) and installation/fitting charges as per Annexure -II (if Repair Both i.e. Ladies & Gent Toilet)		
(b)	MISC Charges if any (i.e. Misc. Items, Labour charges and other items required for repairing work etc.)		
	Sub Total		
	Total GST Charge for above items and works		
	Grand Total		

(Signature of the authorized signatory of the Firm)

Full Name _____

Mobile No. _____

Company Seal _____

Dated: _____

**List of items, required consumable items and other misc. work for repair/renovation
of Ladies & Gents toilet at 3rd floor (Engg. Side) at CERC office,
Chanderlok building, Janpath, New Delhi-110001**

Items required for 3rd Floor Ladies Washroom				
Sl. No.	Particulars	Quantity	Rate Quoted by Bidder for each item	Total
1	PVC 1" Pipe (each length for 10')	10.00		
2	1"x3/4 T	10.00		
3	1" Socket	10.00		
4	1" Elbow .	8.00		
5	1"x 3/4" F. Elbow	8.00		
6	1/2"x3/4" Plane F. Elbow	15.00		
7	3/4" Pipe	6.00		
8	3/4" Cross Over Band	4.00		
9	1/2" x3/4" F. Socket	6.00		
10	1/2"x3/4" F T	6.00		
11	1/2" Plug	10.00		
12	3/4" 25mm Sedal	1.00		
13	CPVC Solvent (237 gm)	1.00		
14	4" Pipe	15 Ft		
15	4" Elbow	7.00		
16	4" Trap	2.00		
17	4" Tee	3.00		
18	Solvent	1.00		
19	M Seal (Big 200gm)	2.00		
20	Tiles (for Thickness of tiles 10mm to 25mm)	40 Sq. ft		
21	Tiles Grouter	2.00		
22	Dust	70 ft		
23	Concreate	50 ft		
24	Cement ISI Mark (50kg each bag)	10 bag		
25	Dismantling of tile work in floors in cement mortar including stacking material within 50 metres lead.	Complete floor Work of 3 rd Floor ladies Toilet Area		
26	Repairing of all damage/seepage area, waterproof work of complete 3 rd floor Ladies Toilet (Engg. Side)	3 rd Floor ladies Toilet Area		
27	Refilling of Filling material in sunken portion from Ground floor to 3rd floor using stairs	3 rd Floor ladies Toilet Area		
28	Disposal of Malba from site (i.e Chanderlok Building, 36, Janpath, New Delhi)	3 rd Floor ladies Toilet Area		
29	Misc Expenses (if any) (i.e. Misc Items, Labour charges etc.)	3 rd Floor ladies Toilet Area		
Grand Total Rs.				

**Items Required for 3rd Floor Ladies & Gents Washroom
(if both washrooms are required to be repair)**

Sl. No.	Particulars	Quantity	Rate Quoted by Bidder	Total
1	PVC 1" Pipe (each length for 10')	25.00		
2	1"x3/4 T Plain	15.00		
3	1" Socket	15.00		
4	1" Elbow .	12.00		
5	1"x 3/4" F. Elbow	20.00		
6	1/2"x3/4" Plane F. Elbow	30.00		
7	3/4" Pipe	12.00		
8	3/4" Cross Over Band	8.00		
9	1/2" x3/4" F. Socket	12.00		
10	1/2"x3/4" F T	12.00		
11	1/2" Plug	24.00		
12	3/4" 25mm Sedal	2.00		
13	CPVC Solvent (500 gm)	2.00		
14	4" Pipe	60 Ft		
15	4" Elbow	12.00		
16	4" Half Set	4.00		
17	4" T	8.00		
18	4" Socket	8.00		
19	4" Trap	4.00		
20	4 1/4 " Pipe	25 Ft		
21	4 1/4 " Elbow	15.00		
22	Solvent	2Ltr		
23	M Seal (Big 200gm)	3.00		
24	Tiles (for Thickness of tiles 10mm to 25mm)	110 Sq. ft		
25	Tiles Grouter	4.00		
26	Dust	150 ft		
27	Concreate	80 ft		
28	Cement ISI Mark (50kg each bag)	25 bag		
29	Dismantling of tile work in floors in cement mortar including stacking material within 50 metres lead.	Complete floor Work of 3 rd Floor Ladies & Gents Toilet Area		
30	Repairing of all damage / seepage area, waterproof work of complete 3 rd floor Ladies & Gents Toilet (Engg. Side)	3 rd Floor ladies & Gents Toilet Area		
31	Refilling of Filling material in sunken portion from Ground floor to 3 rd floor using stairs	3 rd Floor ladies & Gents Toilet Area		
32	Disposal of Malba from site (i.e Chanderlok Building, 36, Janpath, New Delhi)	3 rd Floor ladies & Gents Toilet Area		
33	Misc Expenses (if any) (like; Misc Items/Materials, Labour charges etc.)	3 rd Floor ladies & Gents Toilet Area		
Grand Total Rs.				